

Anonymous Referee n. 1

We would like to thank the reviewer for his/her valuable comments that have helped us improve the manuscript. Please find below our responses to the reviewer's comments.

5 REVIEWER: p1, line 18: not all autonomous dissipative system exhibit period doubling cascade, etc. Think of nondriven mechanical systems in the presence of friction: all motion stops, there is no asymptotic dynamics. The sentence should be reformulated.

RESPONSE: We thank the reviewer for this comment. We have added "in the presence of time-independent forcing", now on p. 1, l. 20 of the revised ms. "[...] in autonomous dissipative systems - in the presence of time-independent forcing - include [...]".

REVIEWER: Fig.1: what is the time t at which the attractors are plotted?

RESPONSE: The attractors are time-independent, but of course only after spinup. Following this useful comment we have now specified the time in the text (p. 5, l. 2): "... and it is plotted at $t = T^* = 400$ yr, i.e. after spinup."

15 REVIEWER: Eq.(5): This quantity is similar to the broadly used finite time Lyapunov exponent. Why do you think that sigma is better suited here?

RESPONSE: The metric sigma provides information that is different from that provided by the Lyapunov exponents. Why have we used sigma here? We had pointed out in this paper's original version - and still do so - that "Pierini et al. (2016) found the quantity sigma to be a good indicator of the degree of sensitivity of the system's evolution with respect to the initial state during the phase of convergence to the attractor." In addition, following this useful comment, we have now stressed, furthermore, that (p. 6, l. 1-4): "The determination of the PBAs of the periodically forced system and the application of the new qualitative and quantitative diagnostic methods proposed in section 4 need an analysis of the behavior of trajectories that lie at $t = 0$ on a given subset Omega of phase space, as is the case when calculating sigma(X,Y) above. Thus, investigating the behavior of model trajectories as they emerge from Omega is the most unifying and distinctive feature of the present model study."

REVIEWER: Fig.2: what is the value of T^* ? How do the plots change if T^* changes? Why exactly this T^* is taken?

RESPONSE: The value of T^* (400 yr) was, and still is, defined in section 2, between Eqs. (3) and (4). The plots of Fig. 2 are independent of T^* provided the latter it is sufficiently greater than the spinup time, but as clearly shown by the graphs of Fig. 3, this is definitely achieved for our choice. Following this useful reviewer's comment, this is now specified on p. 4, l. 11: "... as shown in Fig. 3 and 9 below, T^* is much greater than the spinup time in all cases."

REVIEWER: Fig.3, panel c: this is a chaotic case, and the blue curve cannot be distinguished from the red?

RESPONSE: Yes, the red and blue curves are virtually coincident; this is what happens for trajectories leaving from the very restricted cold-color regions of Fig. 2d; on the other hand, this possibility is not surprising in view of the results of Pierini et al. (2016) (p.7, l. 3): "If $\sigma < 1$, as is the case near P1, the two trajectories are virtually coincident (Fig. 3c)." Of course, these trajectories are nonetheless unstable once they have converged onto the PBA.

REVIEWER: This contradicts Fig.4a where the green points are spread even if started from the vicinity of P1.

40 RESPONSE: We thank the reviewer for this comment. For the response please see p. 8, l. 3-6: "In the chaotic case $\gamma=1.35$, $\sigma \leq 1$ for 43% of the points contained in θ_1 , while $\sigma > 1$ for the remaining points. The evolution of the former lead to the localized blue dots in Figure 4a while the evolution of the latter lead to the green dots scattered over

the strange attractor. The green line of Figure 4b, giving $S_{\theta 1}$ computed with all the trajectories, shows the gradual spreading of the initial points with $\sigma > 1$." Please see also p. 9, l. 7-10 (see a further response below).

REVIEWER: p7, 14: Fig.4a is taken at $t=400$, but the caption says $t=300$. What is the correct statement?

5 RESPONSE: The correct statement in both cases is $t = 300$ y. Thank you.

REVIEWER: Fig.4a: I do not see the red dots mentioned in line 5 of page 7.

10 RESPONSE: As explained in the discussion of Fig. 4a, "...The entropy of the periodic case $\gamma=1.1$, characterized initially by $\sigma < 1$, oscillates between 0 and 1, with the final evolution limited to virtually a single cell over the limit cycle; ...". You can recognize the small cluster at $(\Psi_1, \Psi_2)=(7,12)$, but we understand that this is not easy to be noticed. So, following this useful comment, now we have added a circle in the new Fig. 4a and have mentioned it in the text (p. 8, l. 2): "... with the final evolution limited to virtually a single cell over the limit cycle; the latter cell is enclosed in the red circle of Figure 4a."

15 REVIEWER: Fig.4b,d: I wonder if the use of this entropy is useful if it gives different values for the same chaotic attractor even after 400 time units. We know that S should asymptotically converge to a constant (exactly since the driving is constant). What if we take more initial points in the small square used in Fig.4a?

20 RESPONSE: We thank the reviewer for this comment. For our response please read p. 9, l. 7-10: "Finally, it is worth stressing that, since the forcing is constant, the range of variability of the entropy in the chaotic case with $\sigma > 1$ must tend to zero as the number of points tends to infinity. This tendency is clearly illustrated by the green line of Figure 4d. On the other hand, the range of variability of $S_{\theta 1}$ in the chaotic case (Figure 4b) is still quite large after 400 yr because, as pointed out above, the number of points with $\sigma > 1$ contained in θ_1 is relatively small."

25 REVIEWER: p.8, lines 2-5: you speak about a "sensitive dependence on initial data". I agree, there is some dependence but this is certainly different from the traditional sensitivity since the latter holds on the chaotic attractors. Yours is there for a periodic motion and disappears, as you say in line 5, on the attractor. It might be useful to use a different terminology here.

30 RESPONSE: We thank the reviewer for this comment. Now we have used the expression "sensitive phase dependence on initial data" when referring to the non-chaotic case with $\sigma > 1$. Besides, we have also modified the first paragraph of section 3.2 in order to better characterize this specific form of sensitivity (p. 9, l. 12-20): "We conclude the analysis of the autonomous system by discussing an apparent paradox. We have just seen that, in regions of Γ where $\sigma > 1$, the trajectories for $\gamma = 1.1$ exhibit sensitive phase dependence on initial data, as shown, for instance, by Fig. 3b, by the red dots in Fig. 4c and by the red curve in Fig. 4d. Sensitive dependence on initial data is usually associated with chaotic dynamics, but in this case the dynamics is periodic. This paradox is resolved by noting that such sensitivity concerns only the phase of the periodic trajectories, as already noticed in the previous subsection and, in addition, it occurs only if the initial data lie outside the attractor, e.g, elsewhere on Γ ; on the attractor, this phase sensitivity disappears, as we will show below. On the contrary, in the chaotic case $\gamma = 1.35$, the sensitivity to initial data for trajectories with $\sigma > 1$ always holds, off the attractor as well as on it, in excellent agreement with the chaotic character of the dynamics in the latter case."

35 In any case, in the same section we have clearly explained the fundamental difference between this sensitivity and that associated with chaotic dynamics, so we believe there can be no misunderstanding.

40 REVIEWER: p9, line17: what is the meaning of "spans the attractor roughly six times"?

45 RESPONSE: We have now improved the explanation (p. 10, l. 2-3): "... indeed, these points that start from $t = 300$ yr, evolve anticlockwise around the attractor, covering it roughly six times during the interval $4T_{\Delta} = 100$ yr that separates the first snapshot from the last one."

REVIEWER: Fig.10: What is T and T* here? How do the results depend on their choice?

RESPONSE: Please see p. 15, l. 16-17 for the response to this comment: "... here $T^* = 400$ yr is again the maximum integration time, and $-T \leq \tau \leq T$, while $T = 50$ yr; once more, the following results are independent of T, provided it is sufficiently larger than the typical time scale of the phenomenon."

REVIEWER: Section 5.2: The system treated here is governed by a real pullback attractor. The time-dependence shown in Fig. 17. is a general one but does not possess any drift. Since systems with drift are important in understanding e.g. climate change, the question arises: would $\langle \theta \rangle_{\Gamma}$ be a useful indicator also for this type of systems?

5 RESPONSE: We thank the reviewer for this comment. First of all we have more clearly stated that the new diagnostic method proposed in this study can be applied to a wide class of aperiodically forced systems. Moreover, we have now stressed that the method can find application to the specific, and very interesting case of systems possessing a drift (p. 21, l. 20-21): "For example, this diagnostic method can be applied to study the onset of chaos in systems that possess a drift mimicking global warming and other climate change scenarios (as done, for instance, in Drótos et al., 2015)."

10

REVIEWER: p21, line 7: "In this paper, we studied the transition from nonchaotic to chaotic PBAs in a nonautonomous system whose autonomous limit is is not chaotic. I am lost: is not the attractor of Fig. 1c chaotic?"

15 RESPONSE: But in fact our analysis of section 4 refers to the case $\gamma=1.1$, whose attractor is that of Fig. 1b. This comment is very useful, however, because, to avoid confusion, we followed up on it by specifying that "... chaos is induced by the periodic forcing" (p. 22, l. 3).

20 REVIEWER: p25,line 17: The sentence "the union of quasiperiodic orbits that ... may exhibit a power spectrum that contains a multitude of local variations reminiscent of those exhibited by power spectra of the chaotic orbit" is not convincing. Is the attractor quasiperiodic or chaotic? The blue dots in Fig. A2 do not clarify the situation either. Therefore, here at least I recommend to show this attractor also as the result of a long time series (after an appropriate removal of transients).

25 RESPONSE: This paragraph was not sufficiently clear and it has been revised. We thank the reviewer for pointing out the need for further clarification. In particular, Fig. A3 has been added; this figure illustrates better, and in a more standard way, the distinction between quasi-periodic and chaotic orbits. Please see the new discussion on p. 26, l. 11-24: "By allowing the quasiperiodic trajectories that emanate from D2 to evolve up to $t = 2000$, one obtains the set of blue points shown in Fig. A2. Somewhat surprisingly, this set does not form a closed curve: each blue dot in Fig. A2 corresponds actually to the state at $t = 2000$ in the phase plane of a quasi-periodic orbit. One such orbit is represented in blue in Fig. A1(a), after removal of the transient dynamics. Each blue dot in Fig. A2 corresponds to a different quasiperiodic orbit, whose frequency characteristics may slightly change from one blue dot to another. All these quasiperiodic orbits share, however, a spectral signature that resembles the one shown by the blue curve in Fig. A1(b). To illustrate further the distinction between quasiperiodic and chaotic orbits, the return maps for the minima of the $x(t)$ -variable have been computed. As is well-known (e.g., Strogatz, 2018), if the return map contains just one point, the solution is periodic in time, with all minima having the exact same value, and the period of the oscillation can be estimated by calculating the time interval between two consecutive minima. If the return map contains continuous-looking curves that fill up with more and more points as the length of the orbit increases, the solution is quasi-periodic, while the presence of folds and self-similarity in the return map provides strong evidence for chaotic solutions. For the blue and red trajectories of Fig. A1(a), we plot the corresponding return maps in Figs. A3(a) and (b), respectively. The two plots clearly discriminate between the quasiperiodic nature of the former and the chaotic one of the latter solution."

Anonymous Referee n. 2

We would like to thank the reviewer for his/her valuable comments that have helped us improve the manuscript. Please find below our responses to the reviewer's comments.

5 REVIEWER: Section 3.2 is not needed in my opinion. I wonder if it is correct to interpret a transient growth as a “sensitive dependence on initial conditions”.

RESPONSE: We thank the reviewer for this comment. We have used instead the expression “sensitive phase dependence on initial data” when referring to the non-chaotic case with $\sigma > 1$. Besides, we have also modified the first paragraph of section 3.2 in order to better characterize this specific form of sensitivity (p. 9, l. 12-20): “We conclude the analysis of the autonomous system by discussing an apparent paradox. We have just seen that, in regions of Γ where $\sigma > 1$, the trajectories for $\gamma = 1.1$ exhibit sensitive phase dependence on initial data, as shown, for instance, by Fig. 3b, by the red dots in Fig. 4c and by the red curve in Fig. 4d. Sensitive dependence on initial data is usually associated with chaotic dynamics, but in this case the dynamics is periodic. This paradox is resolved by noting that such sensitivity concerns only the phase of the periodic trajectories, as already noticed in the previous subsection and, in addition, it occurs only if the initial data lie outside the attractor, e.g, elsewhere on Γ ; on the attractor, this phase sensitivity disappears, as we will show below. On the contrary, in the chaotic case $\gamma = 1.35$, the sensitivity to initial data for trajectories with $\sigma > 1$ always holds, off the attractor as well as on it, in excellent agreement with the chaotic character of the dynamics in the latter case.”

In any case, in the same section we have clearly explained the fundamental difference between this sensitivity and that associated with chaotic dynamics, so we believe there can be no misunderstanding.

20 Having said this, we believe that this dynamical behavior deserves to be highlighted. Moreover, at the end of section 4.1 we have pointed out this: “... In our nonautonomous system, the amplitude of the periodic forcing ϵ plays a similar role. This transition to chaos induced by time-dependent forcing appears, therefore, to be directly linked to the existence of regions in phase space in which sensitive dependence to initial data occurs in the limit of periodic solutions. Thus, the chaotic behavior merely due to the time-dependent nature of the forcing can be traced back to the apparently paradoxical property of the autonomous system that was emphasized in Sect. 3.2 This striking observation deserves to be analyzed in greater depth in future studies. ...” We have therefore not removed section 3.2.

REVIEWER: Pg 5, line 4: please use the term “time evolution” instead of “time series”, as in Pierini 2016, throughout the text.

30 RESPONSE: Done. Thank you.

REVIEWER: Pg 5 line 7: (X, Y) is not defined. Is it the initial condition of (Ψ_1, Ψ_3) as in eq. 5?

RESPONSE: Yes, but as you noticed, the definition comes later. Thank you very much. In the revised version, we write “depending on the initial point” (p. 5, l. 11).

35 REVIEWER: Pg 6 line 5: why $\sigma > 1$ initially? $\sigma = 1$ initially by definition (5).

RESPONSE: The reviewer is absolutely right. Thank you very much. We have removed “initially”.

40 REVIEWER: Pg 7, Figure 3c. with $\gamma = 1.35$ you get chaos. How is it possible that two initially close trajectories never diverge?

RESPONSE: Yes, the red and blue curves are virtually coincident; this is what happens for trajectories leaving from the very restricted cold-color regions of Fig. 2d; on the other hand, this possibility is not surprising in view of the results of Pierini et al. (2016). Of course, these trajectories are nonetheless unstable once they have converged onto the PBA because, as noted

45 in section 4.2 "... they will always pass sufficiently near trajectories that are chaotic, thanks to the mixing properties of the [PBA].".

REVIEWER: This contradicts the statement at the beginning of pg 9.

RESPONSE: We thank the reviewer for this comment. Now we have specified that we are referring to cases with $\sigma > 1$ (p. 9, l. 18-20): "On the contrary, in the chaotic case $\gamma = 1.35$, the sensitivity to initial data for trajectories with $\sigma > 1$ always holds, off the attractor as well as on it, in excellent agreement with the chaotic character of the dynamics in the latter case."

5 REVIEWER: Pg 9, line 7 and following lines. I understand that you cannot compute with enough accuracy the first Lyapunov exponent (why? I found it strange for such a low dimensional system). If so, you cannot say that "the results prove unequivocally the assumption."

RESPONSE: We thank the reviewer for this comment. Now we have changed "prove unequivocally" with "are consistent with" (p. 9., l. 25). In the following lines, we explain the typical problems encountered in the computation of the finite-time Lyapunov exponents, but we have not implied that it is impossible to compute them with enough accuracy.

10 REVIEWER: Pg 9 line 11: illustrated instead of summarized.

RESPONSE: Done. Thank you.

REVIEWER: Pg 9 caption of figure 5 and in other parts of the text: "non chaotic".

15 RESPONSE: Done. Thank you.

REVIEWER: Pg 9 line 17: $4T\Delta = 100$

RESPONSE: Done. Thank you.

20 REVIEWER: Pg 10 line 25. It is a contradictory statement. Please explain it better.

RESPONSE: We thank the reviewer for this comment. Please see p.11, l. 11-13: "Recall that the PBAs of a periodically forced system (e.g., Pierini, 2014, and references therein) are always periodic. This periodicity of the PBAs occurs for both periodic and chaotic systems; the latter are typically referred to as cyclostationary. For the sake of simplicity we will refer below to chaotic and non chaotic PBAs, abbreviated as CPBAs and NPBAs, respectively."

25 REVIEWER: Pg 15 eq 10: I do not see the reason to introduce a new symbol for C_{max} . There are already a lot of symbols to keep in mind.

RESPONSE: We thank the reviewer for this comment. We have removed the symbol c_{max} and left only Θ ; see the new Eq. (9).

30 REVIEWER: Pg18, last line: $\langle \Theta \rangle \rightarrow \langle \Theta \rangle \Gamma$

RESPONSE: Done. Thank you.

The onset of chaos in nonautonomous dissipative dynamical systems: A low-order ocean–model case study*

Stefano Pierini^{1,2}, Mickaël D. Chekroun³, and Michael Ghil^{3,4}

¹Università di Napoli Parthenope, Naples, Italy

²CoNISMa, Rome, Italy

³University of California at Los Angeles, Los Angeles, California, USA

⁴Ecole Normale Supérieure and PSL Research University, Paris, France

Correspondence to: Stefano Pierini (stefano.pierini@uniparthenope.it)

Abstract. ~~The~~ A four-dimensional nonlinear spectral ocean model is used to study the transition to chaos induced by periodic forcing in systems that are ~~not non~~ chaotic in the autonomous limit ~~is studied with a four-dimensional nonlinear spectral ocean model~~. The analysis ~~is based on the systematic~~ relies on the construction of the system’s pullback attractors (PBAs) through ensemble simulations ~~derived from~~, based on a large number of initial states in the remote past. A preliminary analysis of the autonomous system is carried out by ~~constructing~~ investigating its bifurcation diagram, as well as by calculating a metric ~~measuring that measures~~ the mean distance between two initially nearby trajectories, along with the system’s entropy. We find that nonchaotic attractors can still exhibit sensitive dependence on initial data over some time interval; this apparent paradox is resolved by noting that the dependence only concerns the phase of the periodic trajectories, and that it disappears once the latter have converged onto the attractor. The periodically forced system, analyzed by the same methods, yields periodic or chaotic PBAs depending on the periodic forcing’s amplitude ε . A new diagnostic method — based on the cross-correlation between two initially nearby trajectories — is proposed to characterize the transition between the two types of behavior. Transition to chaos is found to occur abruptly at a critical value ε_c and begins with the intermittent emergence of periodic oscillations with distinct phases. The same diagnostic method is finally shown to be a useful tool for autonomous and aperiodically forced systems as well.

1 Introduction and motivation

Understanding the mechanisms that lead to the onset of chaos in dissipative dynamical systems is of fundamental importance both from a cognitive viewpoint and for a correct use of the mathematical models on which the systems are based. Chaos arises in such systems as a control parameter in the governing equations crosses a given threshold. A huge amount of work has been devoted to analyzing the transition to chaos in the framework of autonomous dynamical systems, i.e., in systems in which the external forcing and the coefficients do not depend on time. The various routes to chaos in autonomous dissipative systems

*This paper is dedicated to the memory of Anna Trevisan and to her contributions to the applications of dynamical systems theory to the climate sciences.

— in the presence of time-independent forcing — include period doubling cascade, intermittency and crisis, **quasi-periodic** **quasiperiodic** routes, global bifurcations (e.g., Strogatz, 1994; Nicolis, 1995; Hilborn, 2000; Ott, 2002; Tél and Gruiz, 2006).

Nonautonomous dissipative dynamical systems represent a crucial extension of autonomous systems for practical applications, since the external forcing in most real systems — whether deterministic, random or both — depends, typically, on
5 time. Despite their importance, nonautonomous systems have received, until recently, less attention than autonomous systems. Transition to chaos induced by time-dependent forcing has, nonetheless, been studied in several significant cases. A classical example is the Van der Pol oscillator (Van der Pol, 1920, 1926), in which chaotic relaxation oscillations emerge under the effect of an external periodic forcing. A few more recent examples in the climate sciences include (i) transition to chaos due to **quasi-periodic** **quasiperiodic** forcing (Le Treut and Ghil, 1983; Ghil, 1994); (ii) modification of the autonomous transition by
10 periodic forcing (Sushama et al., 2007); and (iii) the important contributions of Anna Trevisan and colleagues to the data assimilation problem for chaotic systems, in which the data stream can be seen essentially as a time-dependent forcing (Trevisan and Uboldi, 2004; Carrassi et al., 2008a, b; Trevisan and Palatella, 2011).

The onset of chaos is analyzed here in the framework of nonautonomous systems, which has recently received rapidly increasing attention in the context of climate dynamics (Ghil et al., 2008; Chekroun et al., 2011; Bódai and Tél, 2012; Bódai
15 et al., 2013; Pierini, 2014; Drótos et al., 2015, 2017; Ghil, 2015, 2017; Pierini et al., 2016; Lucarini et al., 2017). Our study focuses on a four-dimensional nonlinear spectral ocean model (Pierini, 2011), which is subjected to periodic forcing, chosen as the simplest form of time dependence. Cases will be considered that are nonchaotic in the autonomous limit, so that the chaos that emerges in the system is strictly associated with the nonstationarity of the forcing.

The study makes use of ensemble simulations performed with many initial states distributed in a given subset of phase space,
20 following the methodology of Pierini (2014) and Pierini et al. (2016). The overall idea is that the relevant information in the climate system must be derived from statistical analyses of an ensemble of different system trajectories, each corresponding to a different initial state, provided that the corresponding trajectories have converged to the system’s time-dependent attractor.

Such an attractor is called a pullback attractor (PBA; e.g., Ghil et al., 2008; Chekroun et al., 2011; Kloeden and Rasmussen,
25 2011; Carvalho et al., 2012) in the mathematical literature and a snapshot attractor (e.g., Romeiras et al., 1990; Bódai and Tél, 2012; Bódai et al., 2013) in the physical literature; it provides the natural extension to nonautonomous dissipative dynamical systems of the classical concept of an attractor that is fixed in time for autonomous systems. A global PBA is defined as a time-dependent set $\mathcal{A}(t)$ in the system’s phase space that is invariant under its governing equations, along with the equally time-dependent, invariant measure $\mu(t)$ supported on this set, and to which all trajectories starting in the remote past converge (Arnold, 1998; Rasmussen, 2007; Kloeden and Rasmussen, 2011; Carvalho et al., 2012). In the deterministic case, it is understood that $\mathcal{A}(t)$ depends also on the particular forcing, say $F(t)$, that is being applied, but this dependence is usually not kept
30 track of in the notation. In the random case, the PBA is called a random attractor, and the dependence on the specific realization ω of the noise process is often included in the notation, as $\mathcal{A}(t, \omega)$.

Pierini et al. (2016) rigorously proved that a weakly dissipative nonlinear model like the one used there and herein does
35 possess a global PBA, subject to mild integrability conditions on the forcing. In the present study, the numerical approach used for the systematic investigation of the system’s PBAs follows Pierini (2014) and Pierini et al. (2016). Further diagnostic tools

will be introduced for the present periodic-forcing set-up, and a new diagnostic tool will also be proposed to monitor the onset of chaos in our nonautonomous system.

The paper is organized as follows. In Sect. 2, the mathematical model is described. In Sect. 3, the main properties of the autonomous system are summarized and an apparent paradox related to the sensitivity to initial states in the periodic regime is discussed. In Sect. 4, the results obtained for the periodically forced system are presented and discussed; the new cross-correlation-based method specifically formulated to characterize the onset of chaos is introduced and applied to the specific case at hand. This method helps characterize the transition to chaos as the amplitude of the periodic forcing increases, as well as document the coexistence of local PBAs with chaotic and nonchaotic behavior within the model's global PBA. In Sect. 5, the same method is shown to be a useful tool also for autonomous ~~systems and even for some aperiodically forced ones~~ and aperiodically forced systems. Finally, in section 6 the results are summarized and conclusions are drawn. An appendix illustrates in greater detail the coexistence of local PBAs that are chaotic and ~~not-non~~ chaotic in the setting of a periodically forced Van der Pol–Duffing oscillator.

2 Model description

The highly idealized model of the oceans' wind-driven, double-gyre circulation (Ghil, 2017, and references therein) used in the present study is governed by the system of four nonlinear, coupled ordinary differential equations derived by Pierini (2011). ~~This~~; Vannitsem (2014), Vannitsem and De Cruz (2014) and De Cruz et al. (2018) used this model to represent the ocean component in their low-order climate models. The author introduced such a low-order model to complement the process studies on the Kuroshio Extension's low-frequency variability previously carried out with a much more detailed, primitive equation ocean model (e.g., Pierini, 2006; Pierini et al., 2009; Pierini and Dijkstra, 2009). The same low-order model was later used by Pierini (2014) and Pierini et al. (2016) to explore the PBAs of the system in various cases. Here we merely review the main aspects of the model; for all the technical details and parameter values, the interested reader should kindly refer to Pierini (2011).

The dynamics is governed by the evolution equation of potential vorticity in the quasigeostrophic approximation on the beta-plane for a shallow layer of fluid, superimposed on an infinitely deep quiescent lower layer. Pierini (2006) found such a reduced-gravity model to be a good approximation for process studies of the Kuroshio Extension's low-frequency variability (~~LFV~~). The flow is described by the streamfunction $\psi(\mathbf{x}, t)$: like in the previous studies, ψ , the horizontal coordinates $\mathbf{x} = (x, y)$ and the time t are dimensionless, but the dimensional time will be plotted in all the time series presented in this study to emphasize the typical time scales of the oceanic phenomena under investigation.

A four-dimensional spectral model is obtained by expanding the streamfunction in a rectangular domain as follows:

$$\psi(\mathbf{x}, t) = \sum_{i=1}^4 \Psi_i(t) |i\rangle. \quad (1)$$

The orthonormal basis $|i\rangle$ is defined as:

$$|1\rangle = e^{-\alpha x} \sin x \sin y; \quad |2\rangle = e^{-\alpha x} \sin x \sin 2y; \quad |3\rangle = e^{-\alpha x} \sin 2x \sin y; \quad |4\rangle = e^{-\alpha x} \sin 2x \sin 2y$$

where α is a real positive constant. This basis satisfies the free-slip boundary conditions along the borders of the rectangular domain; it also captures the oceanic flow's westward intensification thanks to the exponential factor first introduced in the two-dimensional model of Jiang et al. (1995).

5 The four nonlinear coupled ordinary differential equations that govern the evolution of the vector $\Psi(t) = (\Psi_1, \Psi_2, \Psi_3, \Psi_4)$ can be written, cf. Pierini (2011), as

$$\frac{d\Psi}{dt} + \Psi\mathbf{J}\Psi + \mathbf{L}\Psi = G(t)\mathbf{w}; \quad (2)$$

The coefficients of the nonlinear and linear terms in the equation are encapsulated by the rank-3 and rank-2 tensors \mathbf{J} and \mathbf{L} , respectively, and the forcing is represented by the vector \mathbf{w} , cf. Pierini (2011). The forcing \mathbf{w} is obtained from a suitable double-gyre surface wind stress curl, while G is defined in the present paper to be periodic,

$$10 \quad G(t) = \gamma[1 + \varepsilon \sin(\omega t)], \quad (3)$$

with period $T_p = 2\pi/\omega$, while γ and ε are positive dimensionless parameters.

To construct the system's PBAs, ensembles of forward time integrations are carried out; each of these starts at $t = 0$ from a different initial point contained in a given subset Ω of the model's four-dimensional phase space, and ends at $t = T_* = 400$ yr. as shown in Fig. 3 and 9 below, T_* is much greater than the spinup time in all cases. Following Pierini (2014) and Pierini
15 et al. (2016), the four-dimensional hypercube Ω is defined as:

$$\Psi_1, \Psi_2 \in [-70, 150]; \quad \Psi_3, \Psi_4 \in [-150, 120] \quad (4)$$

and the initial data are all chosen to satisfy $\Psi_1 = \Psi_2$ and $\Psi_3 = \Psi_4$, i.e., to lie within a plane set embedded in Ω .

The ensembles will consist of 15 000 initial data at $t = 0$ that are regularly spaced either in Ω or in a small subset thereof. For the sake of graphical representation, maps of various quantities will be plotted in the rectangle $\Gamma \equiv \{-70 \leq \Psi_1 \leq 150, -150 \leq$
20 $\Psi_3 \leq 120\} \subset \Omega$ that lies in the (Ψ_1, Ψ_3) -plane. In the discussion of the results, we will refer, for the sake of simplicity and concision, to the model's trajectories as being defined in the (Ψ_1, Ψ_3) -plane but, naturally, the actual trajectories evolve in the full four-dimensional phase space.

3 The autonomous system

3.1 The autonomous model's attractors

25 We begin by analyzing some basic properties of the autonomous system that will be useful in the subsequent investigation. The bifurcation diagram of Fig. 1a shows the range of variability of Ψ_1 vs. the forcing parameter γ . The value $\gamma = 1$ corresponds to a global bifurcation that manifests itself by a sudden transition from a small-amplitude limit cycle to a relaxation oscillation with a much higher amplitude. The previous results in this respect (Pierini, 2011; Pierini et al., 2016) will be further bolstered by those in Sect. 5 (Figs. 14 and 15) herein that are based on the diagnostic tool proposed in Sect. 4.2.

Figure 1b shows the limit cycle in Γ arising from arbitrary initial data for $\gamma = 1.1$, which corresponds to the red vertical line in [the bifurcation diagram of panel \(a\)](#). For $\gamma = 1.35$ [the attractor is chaotic](#) (green line in panel (a)) ~~the attractor is chaotic; see Sect. 5.1 further below~~. In this case, the map of the suitably normalized decimal logarithm of the probability density function (PDF) of the trajectories in Γ is plotted in Fig. 1c: ~~it is defined by $q_k(t) = \log_{10}[1000 \times n_k(t)]$. Here n_k is the number of trajectories contained at time t in the k -th cell belonging to the same regular grid of N square cells of width $\Delta\Psi$ that is used in our ensemble simulations, with $N = 15\,000$ and $\Delta\Psi = 2$, and it is plotted at $t = T_* = 400$ yr, i.e. after spinup.~~




Figure 1. Behavior of the autonomous ocean model, for which $\varepsilon = 0$ in Eq. (3). (a) Bifurcation diagram, in which the range of the variable Ψ_1 is plotted vs. the wind stress intensity γ ; the two cases $\gamma = 1.1$ and 1.35 discussed in the text are indicated with a red and a green vertical line, respectively. (b) Limit cycle in the (Ψ_1, Ψ_3) -plane, plotted after spinup, that arises from Γ for $\gamma = 1.1$. (c) [Normalized logarithm Map](#) of the [suitably scaled](#) PDF of [localization of the trajectories in the \$\(\Psi_1, \Psi_3\)\$ -plane for the chaotic case \$\gamma = 1.35\$, using 15 000 trajectories regularly spaced in \$\Gamma\$ at \$t = 0\$ given by \$q_k\$](#) ; see text for details.

In an autonomous dynamical system, the attractors do, by definition, not depend on time, i.e., an attractor is a geometric object in phase space that is fixed in time. However, any attractor that is not a fixed point — whether a limit cycle, torus or strange attractor — can contain time-dependent trajectories. Such ensembles of trajectories arising from specific sets of initial states will be plotted to illustrate the attractors of the autonomous system studied herein.

Following Pierini et al. (2016), in Figs. 2(a,b) the attractors that correspond to the two cases in Figs. 1(b,c) are represented by the time series of $P_{\Psi_3}(t) = \log_{10}(1000 p_{\Psi_3})$ evolution of $P_{\Psi_3}(t) = \log_{10}(1000 \times p_{\Psi_3})$, where $p_{\Psi_3}(t)$ is the PDF of localization of the Ψ_3 -variable; see Pierini et al. (2016) for technical details. The dense distribution of $P_{\Psi_3}(t)$ for $\gamma = 1.35$, as seen in Fig. 2b, is clearly associated with the chaotic character of the flow, while the periodic distribution of $P_{\Psi_3}(t)$ that corresponds to $\gamma = 1.1$ in Fig. 2a is due to the different phases that each trajectory attains on the limit cycle, depending on ~~(X, Y)~~ [the initial point](#).

In Figs. 2(c,d), the same attractors are characterized through the metric σ that was introduced by Pierini et al. (2016); this metric measures the mean divergence of trajectories over the total integration time T_* , and is defined as follows: ~~—~~ The instantaneous Euclidean distance between two initially close trajectories is $\delta(t)$, and its normalized value is given by $\delta_n(t) =$

$\delta(t)/\delta(0)$. Then σ is simply the average of δ_n over T_* ,

$$\sigma(X, Y) = \frac{1}{T_*} \int_0^{T_*} \delta_n(t) dt, \quad \text{with } (X, Y) \equiv (\Psi_1(0), \Psi_3(0)) \in \Gamma. \quad (5)$$

Pierini et al. (2016) found the quantity σ to be a good indicator of the degree of sensitivity of the system's evolution with respect to the initial state during the phase of convergence to the attractor.

- 5 [The determination of the PBAs of the periodically forced system and the application of the new qualitative and quantitative diagnostic methods proposed in section 4 need an analysis of the behavior of trajectories that lie at \$t = 0\$ on a given subset \$\Omega\$ of phase space, as is the case when calculating \$\sigma\(X, Y\)\$ above. Thus, investigating the behavior of model trajectories as they emerge from \$\Omega\$ is the most unifying and distinctive feature of the present model study.](#)




Figure 2. Distinct autonomous regime behavior for (a,c) $\gamma = 1.1$, and (b,d) for $\gamma = 1.35$. Upper panels: time series evolution of P_{Ψ_3} for (a) $\gamma = 1.1$, and (b) $\gamma = 1.35$. Lower panels: maps of the mean normalized distance σ for (c) $\gamma = 1.1$, and (d) for $\gamma = 1.35$; the points $P_1 = (85, 100)$ and $P_2 = (25, 5)$ appear in the panels (c) and (d), respectively. Note the different scales in the two maps; 15 000 trajectories, with regularly spaced initial points in Γ , were used for both maps.

The map of σ in Fig. 2c reveals, in the autonomous case at hand, the same striking features found by Pierini et al. (2016) for the nonautonomous, aperiodic-forcing case, namely the coexistence of extended regions of Γ with $\sigma \leq 1$, shown by cold colors, and with $\sigma > 1$, appearing as warm colors. In the first case, two trajectories that are initially close remain close at all times, as seen in Fig. 3a. In the second case, though, two trajectories that are initially close may attain a large phase difference once they have converged to the attractor, cf. Fig. 3b, while still remaining perfectly coherent.




Figure 3. Typical behavior of time series evolution of $\Psi_3(t)$ for different values of the parameter γ and different initial points in Γ . (a) Two trajectories obtained for $\gamma = 1.1$ and initialized at P_1 (red line) and at a nearby point (blue line). (b) Same as in panel (a), but for two trajectories starting from the point P_2 (red) and near it (blue). (c,d) Same as in (a,b) but for $\gamma = 1.35$.

In the chaotic case with $\gamma = 1.35$, the warm-color regions, in which $\sigma > 1$, overwhelm the cold-color regions, in which $\sigma \leq 1$, cf. Fig. 2d. To illustrate the two types of behavior, Figs. 3(c,d) show the evolution of $\Psi_3(t)$ of two initially nearby trajectories: if $\sigma < 1$, as is the case near P_1 , the two trajectories are virtually coincident (Fig. 3c). If, on the other hand, $\sigma > 1$ initially, as is the case near point P_2 , the two aperiodic signals become incoherent lose their coherence (Fig. 3d). Finally, it is worth noting that, for simulations with sufficiently small γ (not shown), $\sigma < 1$ everywhere.

A different and useful way of looking at these two types of behavior is to analyze the corresponding mixing properties of the flow in the model's phase space. To do so, one can make use of the system's entropy (Shannon, 1948):

$$S_{\vartheta}(t) = - \sum_{k=1}^N p_k \ln p_k. \quad (6)$$

Here Γ is decomposed into a regular grid of N square cells of width $\Delta\Psi$ — with $N = 15\,000$ and $\Delta\Psi = 2$, so that the grid corresponds to that of the initial data used in our ensemble simulations — and $p_k(t)$ is the probability of localization in the k -th cell at time t of the trajectories emanating at time $t = 0$ from a given subset $\vartheta \subset \Gamma$.

Figure 4a shows the intersection with the (Ψ_1, Ψ_3) -plane at $t = 400t = 300$ yr of 15 000 trajectories originating from the box ϑ_1 that coincides with the $\Delta\Psi \times \Delta\Psi$ grid cell centered at P_1 ; the red dots correspond to the case $\gamma = 1.1$ and the green dots to $\gamma = 1.35$. Figure 4b shows S_{ϑ_1} for the two cases; note that $S_{\vartheta_1}(0) = 0$ since all the initial states lie in the single cell ϑ_1 , and thus $p_1 = 1$. The entropy of the periodic case $\gamma = 1.1$, characterized initially characterized by $\sigma < 1$, oscillates between 0 and 1, with the final evolution limited to virtually a single cell over the limit cycle; on the contrary, the chaotic case leads to the trajectories' being the latter cell is enclosed in the red circle of Figure 4a.

In the chaotic case $\gamma = 1.35$, $\sigma < 1$ for 43% of the points contained in ϑ_1 , while $\sigma > 1$ for the remaining points. The evolution of the former lead to the localized blue dots in Figure 4a while the evolution of the latter lead to the green dots scattered over the chaotic attractor, with the entropy (green line in Fig. strange attractor. The green line of Figure 4b) reaching large values, giving S_{ϑ_1} computed with all the trajectories, shows the gradual spreading of the initial points with $\sigma > 1$.

Figures 4(c,d) show the same quantities for the initial $\Delta\Psi \times \Delta\Psi$ box ϑ_2 centered at P_2 . The chaotic case is similar to that for ϑ_1 , but with a greater entropy; on the other hand, the periodic case differs in that now $\sigma > 1$ initially, cf. Fig. 2c. Figure 4c shows that the asymptotic evolution of the very small ϑ_2 covers a limited but significant part of the limit cycle, as seen by comparing this figure with Fig. 1b; the corresponding entropy in Fig. 4d eventually oscillates periodically between the values $S_{\vartheta_2} \sim 2.2 - 3.7$. Figure 4 thus demonstrates clearly the usefulness of the metric σ in characterizing subsets of Γ and the effect of the control parameter γ .

Finally, it is worth stressing that, since the forcing is constant, the range of variability of the entropy in the chaotic case with $\sigma > 1$ must tend to zero as the number of points tends to infinity. This tendency is clearly illustrated by the green line of Figure 4d. On the other hand, the range of variability of S_{ϑ_1} in the chaotic case (Figure 4b) is still quite large after 400 yr because, as pointed out above, the number of points with $\sigma > 1$ contained in ϑ_1 is relatively small.

3.2 An apparent paradox

We conclude the analysis of the autonomous system by discussing an apparent paradox. We have just seen that, in regions of Γ where $\sigma > 1$, the trajectories for $\gamma = 1.1$ exhibit very sensitive sensitive phase dependence on initial data, as shown, for instance, by Fig. 3b, by the red dots in Fig. 4c and by the red line-curve in Fig. 4d. This property Sensitive dependence on initial data is usually associated with chaotic dynamics, but in this case the dynamics is periodic.

This paradox is resolved by noting that such sensitivity concerns only the phase of the periodic trajectories, as already noticed in the previous subsection and, in addition, it occurs only if the sensitive dependence occurs while the initial data are distributed over all of lie outside the attractor, e.g. elsewhere on Γ ; once a trajectory has converged onto on the attractor, the sensitivity of the dependence this phase sensitivity disappears, as shown we will show below. On the contrary, for in the chaotic case $\gamma = 1.35$, the highly sensitive dependence on the initial data sensitivity to initial data for trajectories with $\sigma > 1$ always




Figure 4. Chaotic and ~~not~~non chaotic behavior of the autonomous model, for time-independent forcing intensity $\gamma = 1.1$ (red) and $\gamma = 1.35$ (green), respectively. Typical behavior of (a,c) the trajectories in the model's phase plane (Ψ_1, Ψ_3) ; and (b,d) of the model's entropy $S_\theta(t)$. (a) Intersection with the (Ψ_1, Ψ_3) -plane at $t = 300$ yr of 15 000 trajectories emanating from the small square box ϑ_1 of width $\Delta\Psi = 2$ and centered at the point P_1 (black dot), for $\gamma = 1.1$ (red dots, enclosed in the red circle) and for $\gamma = 1.35$ (green dots); for the blue dots see the text. (b) Time series evolution of the corresponding entropy S_{ϑ_1} for $\gamma = 1.1$ (red line) and $\gamma = 1.35$ (green line). (c,d) Same as panels (a,eb), but for the initial box ϑ_2 centered at P_2 , likewise shown as a black dot in (c). For the evolution of the points contained at $t = 300$ yr in the black rectangle of panel (c), see Fig. 5 below.

holds, on-off the attractor as well as off-on it, in excellent agreement with the chaotic character of the dynamics in this-the latter case.

We must show, therefore, that the trajectories are stable for $\gamma = 1.1$ and unstable for $\gamma = 1.35$, once they have settled onto the attractor. This distinction between the two cases can already be inferred from Figs. 3 and 4 but it is worth investigating
 5 the issue in greater detail. The usual quantitative approach relies on the computation of the mean-leading finite-time Lyapunov exponent λ of each trajectory (e.g., Ott, 2002).

The results (not shown) ~~prove unequivocally~~ are consistent with the assumption above, but the exponents are highly dependent (i) on the time T_λ over which the finite-time exponents are computed; ~~and (ii), and~~ and on the amplitude of the perturbation superimposed on the reference trajectory at each time step T_λ . Moreover, the assumption of exponential divergence of chaotic trajectories is not fully met in our highly nonlinear framework, so that the transition between periodic and chaotic dynamics may actually occur at a value of λ that is not exactly equal to 0. A qualitative ~~but more robust diagnostic~~ method is instead ~~summarized~~ illustrated in Fig. 5, and we propose, furthermore, in Sect. 4 an alternative quantitative method.




Figure 5. Chaotic and ~~not non~~ chaotic behavior of the autonomous model. (a) Evolution of the 1774 points (red dots) contained at $t = 300$ yr in the black rectangle of Fig. 4c for $\gamma = 1.1$; the attractor is illustrated by the entire set of 15 000 points, shown in light red. (b) Same but for the 135 points (green dots) that lie within the same rectangle for $\gamma = 1.35$; in this case, the attractor composed of the 15 000 points is shown in light green. Due to the chaotic nature of the dynamics in this case, only one snapshot, after 25 yr, is drawn.

Let us consider the points lying in the black rectangle shown in Fig. 4c at $t = 300$ yr: the corresponding evolution at four subsequent time instants, $T_\Delta = 25$ ~~years-yr~~ apart, is shown in Fig. 5a for $\gamma = 1.1$ (red dots). Note that the period of the orbits on the attractor is $T_{p^*} = 14.08$ yr, i.e. $T_\Delta > T_{p^*}$.

10 The stability of the trajectories under consideration is clearly demonstrated in Fig. 5a ~~is clearly demonstrated~~ by the compact form and limited extent of the cluster ~~of points in its evolution, which spans the attractor: indeed, these points that start from $t = 300$ yr, evolve anticlockwise around the attractor, covering it roughly six times in $4\Delta = 100$ yr. during the interval $4T_\Delta = 100$ yr that separates the first snapshot from the last one.~~ On the contrary, Fig. 5b shows that for $\gamma = 1.35$ (green dots) the compact form of the initial cluster is lost already after a single 25-yr lapse of time. The trajectories will thus soon be

15 scattered over the strange attractor, due to their divergence.

In conclusion, our autonomous system becomes chaotic for sufficiently large values of γ , e.g., for $\gamma = 1.35$. The system's periodic regime spans a range of γ that includes the bifurcation at $\gamma = 1$, which is apparent in Fig. 1a.

We have shown, moreover, when $\gamma = 1.1$, that regions of Γ exist within which the mean normalized distance σ between two initially nearby trajectories is larger than unity; see again Fig. 2c. In this case, despite the attractor's being a limit cycle, the trajectories leaving from such regions of phase space experience sensitive phase dependence on the initial data. ~~This property, Although sensitive dependence is~~ typically associated with chaotic systems, this sensitivity is not in contradiction with the periodic character of the solutions: as a matter of fact, the trajectories under discussion are stable and the sensitive dependence disappears once the trajectories have converged onto the attractor.

The existence of regions with $\sigma > 1$ for an autonomous periodic system is an important feature for the transition to chaos when the system is subjected to time-dependent forcing: this issue will be discussed in the next section. Besides, the new diagnostic method introduced in Sect. 4.2 to help analyze transition to chaos in the non-autonomous case ~~is~~ will be applied in Sect. 5.1 to the autonomous case.

4 The periodically forced system

For the idealized double-gyre model governed by Eq. (2), we have seen that the autonomous system given by $\varepsilon = 0$ in Eq. (3) exhibits a limit cycle when $\gamma = 1.1$; this limit cycle corresponds to the large-amplitude relaxation oscillation of Fig. 1b. On the other hand, Pierini (2014) showed that, when the same model, with the same value of γ , is subjected to periodic forcing with $\varepsilon = 0.2$ and $T_p = 30$ yr, it exhibits chaotic, cyclostationary and cycloergodic behavior; see figures 2 and 3 therein and the related discussion. To understand the transition to deterministically chaotic behavior induced by the forcing, we will now apply in Sect 4.1 the methodology used in Sect. 3 to the PBAs corresponding to $\gamma = 1.1$ and $T_p = 30$ yr across the intervening parameter range $0 \leq \varepsilon \leq 0.2$. In Sect. 4.2, the transition to chaos induced by the periodic forcing will be analyzed in greater detail through an additional method here developed explicitly for this purpose.

4.1 The pullback attractors of the forced system

Recall that the PBAs of a periodically forced system (~~e.g., Pierini, 2014~~) (e.g., Pierini, 2014, and references therein) are always periodic, ~~but can be either themselves periodic — in which case all trajectories are periodic and there is no mixing — or chaotic, in which case aperiodic trajectories emerge and, therefore, mixing is present. We~~. This periodicity of the PBAs occurs for both periodic and chaotic systems; the latter are typically referred to as cyclostationary. For the sake of simplicity we will refer below to chaotic and ~~nonchaotic non~~ chaotic PBAs, abbreviated as CPBAs and ~~NCPBAs~~ NPBAs, respectively.

For the autonomous case, the time series evolution of $P_{\Psi_3}(t)$ and the map of $\sigma(X, Y)$ — already shown in Figs. 2a and 2c, respectively — are again plotted in Figs. 6a and 6e for the sake of comparison; Figs. 6d,h correspond to the CPBA studied by Pierini (2014), ~~but in that case ε was multiplied by the aperiodic forcing shown in Fig. 17 below.~~ Two intermediate cases that correspond to $\varepsilon = 0.05$ and $\varepsilon = 0.1$ are shown in Figs. 6b,f and Figs. 6c,g, respectively. In Sect. 4.2, we will show in greater detail that the transition to chaotic behavior occurs abruptly, when crossing a critical value ε_c that lies between the two intermediate values of 0.05 and 0.1; here we merely provide some qualitative arguments showing that, in fact, the case $\varepsilon = 0.05$ is still periodic, while the case $\varepsilon = 0.1$ is chaotic.




Figure 6. Transition from a periodic to a chaotic PBA as the amplitude ε of the periodic forcing in Eq. (3) increases. (a,b,c,d) Time series evolution of P_{Ψ_3} ; and (e,f,g,h) maps of σ for $\gamma = 1.1$, $T_p = 30$ yr and $\varepsilon = 0, 0.05, 0.1$, and 0.2 , respectively.

Figure 7 provides further information on the four cases illustrated in Fig. 6. In Figs. 7a–d, the magenta dots represent the intersection with the (Ψ_1, Ψ_3) -plane at $t = 400$ yr of 15 000 trajectories, whose initial points (in blue) are evenly distributed in Γ at $t = 0$; in addition, in Figs. 7e–h, the corresponding entropy $S_{\vartheta=\Gamma}$ is plotted as a function of time, along with the number n_o of cells that are occupied by at least one point. Clearly, the structure of the PBA snapshot in Fig. 7b, for $\varepsilon = 0.05$, is very similar to that of the autonomous case in Figs. 1b and 7a, while the PBA snapshots plotted at $t = 400$ yr — for $\varepsilon = 0.1$ and 0.2 in Figs. 7c and 7d, respectively — are quite different.

To understand better this difference, we focused in Fig. 8 on the subdomain ϑ_2 of Γ that was defined in Fig. 4c and for which $\sigma > 1$. The autonomous case has already been analyzed in Sect. 3.1: in fact, Figs. 8a,e are equivalent to Figs. 4c,d. In the case of $\varepsilon = 0.05$, the same behavior is found, i.e., the sensitivity to initial data leads to only a compact subset of the attractor being covered; this implies the periodicity of the trajectories.

On the contrary, for $\varepsilon = 0.1$ the intersection of the trajectories at $t = 400$ yr with the (Ψ_1, Ψ_3) -plane, shown by the magenta dots in Fig. 8c, is virtually indistinguishable from the one that appears in Fig. 7c, when the initial data are selected in the whole of Γ : this excellent match is an unequivocal sign of the mixing property of chaotic dynamics, as already discussed for the autonomous case $\gamma = 1.35$ in connection with Figs. 4 and 5. That the same property holds for $\varepsilon = 0.2$ in Fig. 8d is not surprising, since Pierini (2014) already recognized the model’s chaotic behavior for this parameter value.

Finally, it is instructive to visualize $\Psi_3(t)$ for a couple of trajectories that are very close at $t = 0$, as done in Fig. 3 for the autonomous case. Figure 9 shows $\Psi_3(t)$ for the four cases of Figs. 6–8 and for trajectories that emerge from ϑ_2 . In Figs. 9a,b the two trajectories are periodic, but with a phase difference. In the two chaotic cases of $\varepsilon = 0.1, 0.2$ in Figs. 9c,d, both trajectories




Figure 7. Intersection with the (Ψ_1, Ψ_3) -plane at $t = 400$ yr (magenta dots) of 15 000 trajectories emanating from Γ at $t = 0$ for $\gamma = 1.1$ and $T_p = 30$ yr. The complete set of the initial points covering Γ is in blue. Top panels: (a) $\epsilon = 0$, (b) 0.05, (c) 0.10, and (d) 0.2. ~~The complete set of the initial points covering Γ is in blue.~~ Bottom panels: (e,f,h,g) the corresponding entropy S_{ψ_2} is plotted, along with the number n_o of occupied cells.

are clearly aperiodic. In Fig. 9c, though, i.e., in the case that is closer to the transition, this aperiodicity is merely associated with a temporary shift in phase of an otherwise periodic signal within the intervals $t \simeq 40 - 120$ yr and $t \simeq 360 - 400$ yr.

The intermittent behavior seen in Fig. 9c appears — from many simulations that are not shown here — to be typical of chaotic solutions near the transition point ϵ_c and suggests a possible mechanism through which chaos is induced by an external periodic forcing. For values of ϵ just past ϵ_c , the model still tends to behave periodically, but the external forcing is sufficiently strong to entrain a trajectory occasionally into a nearby region, where the periodicity is preserved but the phase differs by a finite amount. Since these shifts are very sensitive to the initial data, the result is a chaotic trajectory characterized by separate intervals of periodic oscillations with a different phase. This mechanism also explains why the transition to chaos leads to a notable increase of the measure of the regions in Γ where sensitive dependence to initial data occurs; such an increase is visually obvious when comparing Figs. 6e,f with Figs. 6g,h. As ϵ increases further, the duration of the intervals of constant phase decreases, and the oscillations tend to become more genuinely aperiodic, as seen in Fig. 9d.

This behavior is similar to the intermittency found in autonomous dissipative systems (e.g., Manneville and Pomeau, 1979; Pomeau and Manneville, 1980), in which a trajectory switches back and forth from periodic to aperiodic oscillations provided a certain control parameter of the system — e.g., the amplitude of the steady, time-independent forcing — crosses a given threshold. In our nonautonomous system, the amplitude of the periodic forcing ϵ plays a similar role. This transition to chaos




Figure 8. Same as Fig. 7, but for 15 000 trajectories emanating at $t = 0$ from the small rectangle ϑ_2 of width $\Delta\Psi = 2$ centered at P_2 .

induced by time-dependent forcing appears, therefore, to be directly linked to the existence of regions in phase space in which sensitive dependence to initial data occurs in the limit of periodic solutions. Thus, the chaotic behavior merely due to the time-dependent nature of the forcing can be traced back to the apparently paradoxical property of the autonomous system that was emphasized in Sect. 3.2. This striking observation deserves to be analyzed in greater depth in future studies.

5 4.2 Transition to chaos studied by a cross-correlation method

Recognizing qualitatively whether a PBA is chaotic or not is relatively simple; e.g., this can be done through the heuristic arguments illustrated in Fig. 4 and Fig. 5 and through those outlined in the previous subsection and illustrated in Figs. 6–9. But how to characterize the transition from periodic to chaotic dynamics as a control parameter, such as the amplitude ε of the periodic forcing, changes?

- 10 We have already discussed in Sect. 3.1 the limitations of using the mean finite-time Lyapunov exponents. Here we propose a new, simple and robust method that is particularly useful in our periodic-forcing case, but can be applied also to any autonomous system and even to aperiodically forced systems; the latter ~~situation~~situations will be addressed in Sect. 5. In Secs. 3 and 4.1, we have relied on the mixing properties of chaotic dynamics, as measured by the system's entropy S_ϑ , to recognize the occurrence of chaotic behavior. Now we rely on the emergence of aperiodic signals from a subset of Γ ; this subset will necessarily be
- 15 contained in the region where sensitive dependence on initial data occurs, i.e., where $\sigma > 1$.




Figure 9. Increasing instability of trajectories as ε increases. Time series evolution of $\Psi_3(t)$ for the trajectory initialized at the point P_2 (red line) and at a nearby point (blue line) for $\gamma = 1.1, T_p = 30$ yr, and (a–d) $\varepsilon = 0, 0.05, 0.1$, and 0.2 .

The most obvious approach would be to compute the power spectrum of each trajectory. Periodic signals can, however, be quite complex, as seen, for instance, in Figs. 9a,b; this complexity makes it quite difficult to identify a parameter whose value will distinguish, accurately and reliably, between periodic and chaotic dynamics, based solely on the Fourier spectra of a finite number of finite-length trajectories.

- 5 We propose a much-simpler alternative method that takes advantage of the ensemble simulations carried out to obtain numerically the PBAs. Let $\bar{\Psi}_3$ and ζ_3 be the mean and root-mean square values of the time series $\Psi_3(X, Y, t)$, and consider the centered and normalized anomaly time series $\tilde{\Psi}_3(X, Y, t)$ and $\tilde{\Psi}_3(X', Y', t)$, of Ψ_3 , with

$$\tilde{\Psi}_3 = \frac{\Psi_3 - \bar{\Psi}_3}{\zeta_3}, \quad (7)$$

- 10 where (X, Y) and (X', Y') are two points in Γ that are near to each other, and from which these two time series emerge at $t = 0$. We can then compute the cross-correlation between the two signals, after removing the initial transient, as

$$c(X, Y, \tau) = \frac{1}{T_* - 2T} \int_T^{T_* - T} \tilde{\Psi}_3(X, Y, t) \tilde{\Psi}_3(X', Y', t + \tau) dt; \quad (8)$$

here $T_* = 400$ yr is again the maximum integration time, and $-T \leq \tau \leq T$, while $T = 50$ yr; once more, the following results are independent of T , provided it is sufficiently larger than the typical time scale of the phenomenon. Note also that, in the above definition, we have dropped the dependence of c on (X', Y') for the sake of conciseness.

Now, if $\sigma < 1$, the two signals are periodic and virtually coincident, as seen, for instance, in Fig. 3a,c. Hence, defining the maximal cross-correlation by

$$\Theta(X, Y) = \max \{c(X, Y, \tau) : \tau \in [-T, T]\}, \quad (9)$$

one will have $e_{\max} \cong 1$, with $e_{\max} \Theta(X, Y) \cong 1$, with Θ being attained at $\tau = 0$.

5 On the other hand, if $\sigma > 1$, there are two possibilities:

– either the PBA is not chaotic, in which case all couples (X, Y) and (X', Y') yield two periodic and virtually equal signals, apart from a finite phase difference, as seen, for instance, in Figs. 3b and 9a,b; in this case, again, $e_{\max} \cong 1 \Theta \cong 1$, which will now occur at some lag $\tau \neq 0$ that depends on the phase difference;

– or the PBA is chaotic, in which case ~~some couple yields~~ all couples yield two aperiodic and significantly different signals, as seen, for instance, in Figs. 3d and 9c,d; in this case, $e_{\max} \Theta$ will be substantially less than unity.

This alternative is illustrated in Fig. 10, ~~with the window length $T = 50$ yr in Eq. ,~~ for the four couples of trajectories plotted in Figs. 9a–d, all of which were initialized in ϑ_2 , where $\sigma > 1$.




Figure 10. Cross-correlation $c(\tau)$ between the two initially nearby trajectories shown in Figs. 9a–d, computed for the centered and normalized anomalies $\tilde{\Psi}_3$, according to Eq. (7), for $\varepsilon = 0$ (red line), 0.05 (orange line), 0.1 (green line), and 0.2 (blue line).

It is then useful to analyze the maps of the parameter Θ , ~~defined as~~

$$\Theta(X, Y) = c_{\max}(X, Y).$$

15 Figures 11a-d show Θ for the four cases of Figs 6–9. In the two cases that we have already identified as nonchaotic, Θ varies within a range of values $[0.95, 1.1]$ that lies very close to unity, as expected; see Figs. 11a,b. There is only a small neighborhood of $P_0 = (-16, -83)$ in which Θ is very small: this is because P_0 in the autonomous case is a fixed point; see Fig. 12.

The two cases that we have identified as chaotic appear here as Figs. 11c,d, and in them Θ exhibits in fact smaller values. These values lie in the range $[0.2, 0.8]$ for a large subset of the domain, where $\sigma > 1$, as shown in Figs. 6g,h. Regions in which $\sigma > 1$ but $\Theta \simeq 1$ are present as well, but the corresponding trajectories are nonetheless unstable once they have converged onto the PBA, because they will always pass sufficiently near trajectories that are chaotic, thanks to the mixing properties of the latter.




Figure 11. PBA diagnostics for $\gamma = 1.1$ and $T_p = 30$ yr, with $\varepsilon = 0, 0.05, 0.1$, and 0.2 , respectively, for the two sets of four maps. Upper-row panels (a–d) show the field of $\Theta(X, Y)$, as defined in Eq. (9); the color bar for the $\Theta(X, Y)$ -values is shown to the right of each panel, and it extends over the range $[0.1, 1.12]$. Lower-row panels (e–h) show the field of $\Phi(X, Y)$, as defined in Eq. (10), with the threshold value $\Theta_0 = 0.8$; here $\Phi = 1$ is colored yellow; $\Phi=2$ is green, and $\Phi = 3$ is red. The corresponding maps of $\sigma(X, Y)$ appear in Figs. 6(e–h), respectively.




Figure 12. Fixed point P_0 of the autonomous case, with $\varepsilon = 0$. Time series evolution of Ψ_3 for the trajectory initialized at $P_0 = (-16, -83)$ (blue line) and at a nearby point (solid red line) for $\gamma = 1.1$ and $T_p = 30$ yr .

In summary, if $\Theta \sim 1$ everywhere (yellow colors) we have an NCPBA-NPBA, whereas — if Θ yields values that are sufficiently smaller than unity (grey colors) — then we have a CPBA. ~~Note that the latter case is possible only where $\sigma > 1$.~~

To summarize in a clear and simple way the information provided by the values of both σ and Θ , we introduce the integer-valued parameter Φ , defined as follows:

$$\Phi(X, Y) = \begin{cases} 1 & \text{if } \sigma \leq 1 \quad (\text{yellow}) \\ 2 & \text{if } \sigma > 1 \quad \text{and} \quad \Theta > \Theta_0 \quad (\text{green}) \\ 3 & \text{if } \sigma > 1 \quad \text{and} \quad \Theta \leq \Theta_0 \quad (\text{red}). \end{cases} \quad (10)$$

Here Θ_0 is a threshold value and $\Phi(X, Y)$ is plotted in Figs. 11e–h for $\Theta_0 = 0.8$.

~~For example, As an example of the usefulness of Φ , let us note that~~ the σ -maps in Figs. 6f and 6g are fairly similar, except for the more extended warm-color region, where $\sigma > 1$, in the second map. Recall, however, that the meaning of $\sigma > 1$ is profoundly different if the system is chaotic, in which case mixing is present, as opposed to when it is not, in which case sensitive dependence to initial data concern only the phase of the signal and is not accompanied by mixing.

~~Transition from periodic to chaotic behavior, illustrated by the metric $\langle \Theta \rangle_\Gamma$ plotted vs. the amplitude ϵ of the periodic forcing in Eq. ; $\gamma = 1.1$ and $T_p = 30$ yr.~~

This ambiguity is resolved by the use of the step function Φ : if $\epsilon = 0.05$ (Fig. 11f), sensitive dependence to initial data, i.e. $\sigma > 1$, yields the value of $\Phi = 2$ (green regions), since $\Theta \simeq 1$, which tells us that the system is not chaotic. On the contrary, if $\epsilon = 0.1$ (Fig. 11g), regions with $\Phi = 2$ (in red) appear within the green regions: this implies low Θ -values and therefore chaos.

We conclude by analyzing the transition from NCPBA-NPBAs to CPBA's via a suitable function of the control parameter ϵ : this metric is provided by the average value $\langle \Theta \rangle_\Gamma$ of Θ over Γ . The graph of $\langle \Theta \rangle_\Gamma(\epsilon)$ in Fig. 13 is obtained by performing many ensemble simulations of system trajectories with many distinct values of ϵ ; the latter values are chosen to lie closer to each other where the variation of $\langle \Theta \rangle_\Gamma(\epsilon)$ is stronger. An abrupt transition from NCPBA-NPBAs, with $\langle \Theta \rangle_\Gamma \simeq 1$, to CPBA's occurs at $\epsilon_c \cong 0.09$. Many additional analyses (not shown) for values just below and above ϵ_c confirm that this is in fact the critical value beyond which chaos sets in.

5 Further applications of cross-correlation diagnostics

5.1 Application to the autonomous system

The diagnostic method proposed in Sect. 4.2 to monitor the transition from NCPBA-NPBAs to CPBA's in periodically forced systems relies on two properties: (i) in an NCPBA-NPBA all trajectories are periodic; and (ii) in a CPBA diverging aperiodic trajectories emerge from at least one a subset of Γ , in which necessarily $\sigma > 1$. Thus, the same cross-correlation-based method can obviously be applied to an autonomous system as well. The method's application to the autonomous model studied in Sect. 3 will shed new light on the periodic vs. chaotic character of its solutions.




Figure 13. [Transition from periodic to chaotic behavior, illustrated by the metric \$\langle \Theta \rangle_{\Gamma}\$, plotted vs. the amplitude \$\varepsilon\$ of the periodic forcing in Eq. \(3\); \$\gamma = 1.1\$ and \$T_p = 30\$ yr.](#)

The graph in Fig. 14 shows $\langle \Theta \rangle_{\Gamma}(\gamma)$ and is obtained, like that of Fig. 13, by performing many ensemble simulations, each with a different value of γ , rather than ε , which equals zero in the present case. The first thing to notice is the sudden drop of $\langle \Theta \rangle_{\Gamma}$ at $\gamma = \gamma_c = 1$, where a global bifurcation separates small-amplitude limit cycles from large-amplitude relaxation oscillations, as shown in Pierini (2011) and in Sect. 3.1 here. In addition, Pierini (2012) investigated the stochastic version of this deterministic tipping point in the case of random forcing.

The chaotic nature of the attractor for γ_c is illustrated in Fig. 15. For $\gamma = 0.99$, the Ψ_3 -time series exhibits the typical small-amplitude, purely periodic behavior studied in subsection 3.1, while for $\gamma = 1$ both small- and large-amplitude oscillations occur irregularly in the same time series. The behavior at $\gamma = 1.01$ illustrates the return to more regular behavior.

Thus, chaotic dynamics occurring in an extremely restricted γ -range separates two different types of limit cycles. Figure 16 shows this dramatic transition in terms of σ : the chaotic nature of the flow for $\gamma_c = 1$ is such that the warm-colored regions in which $\sigma > 1$ overwhelm the cold-colored regions, as in Fig. 2d, where $\gamma = 1.35$.

For $\gamma > 1$, the system is not chaotic — except for limited γ -intervals centered at $\gamma \simeq 1.25$ and $\gamma \simeq 1.335$ — until a new abrupt drop of $\langle \Theta \rangle_{\Gamma}$ at $\gamma = \gamma_0 = 1.3475$, shown by a dashed black line in Fig. 14. This drop signals the presence of chaotic attractors beyond γ_0 ; in particular, the chaotic case $\gamma = 1.35$, shown by the solid green line and discussed in Sect. 3, lies just after this transition. It is worth noting the large fluctuations dominate the chaotic regime.




Figure 14. Same as Fig. 13, but for the autonomous model with $\varepsilon = 0$ and the amplitude γ of the time-independent forcing on the abscissa. The vertical red and green lines denote the periodic and the chaotic cases, respectively, that were analyzed in Sect. 3.1; see again Fig. 1. Please see the text for the interpretation of the dashed lines corresponding to $\gamma_c = 1$ and $\gamma_0 = 1.3475$.




Figure 15. Critical transition in the autonomous system at γ_c . Panels (a,d), (b,e) and (c,f) correspond to $\gamma = 0.99, 1.0$ and 1.01 , respectively. (a,b,c) Time series evolution of Ψ_3 for the trajectory initialized at P_1 (red line) and at a nearby point (blue line); (d,e,f) same but for trajectories initialized at P_2 .




Figure 16. Critical transition in the autonomous system at γ_c , illustrated by maps of the mean normalized distance σ for $\gamma = 0.99, 1.0, 1.01$.

5.2 Application to an aperiodically forced system

Our cross-correlation diagnostics ~~assumes that NCPBAs are periodic: this holds for the periodically forced case in Sect. 4.2, as well as for the autonomous case in Sect. 5.1. Thus, the method does not seem, on the face of it, to be applicable to the more realistic case of nonautonomous systems forced by an aperiodic or random process. In the present subsection, though, we will~~ show that the method might still work by applying it to the aperiodically forced system of Pierini et al. (2016) has been shown to apply to both periodically forced and autonomous systems. Its validity, however, is even more general, since it extends to a large class of aperiodically forced systems as well. We choose the model setup of Pierini et al. (2016) to illustrate the latter possibility. A thorough analysis of this application is beyond the scope of the present study: we will therefore limit ourselves to analyzing the basic aspects of the problem, and leave the details for a future ~~study-investigation.~~

Pierini et al. (2016) considered the same system — governed by Eq. (2), and within the same parameter regime adopted here and in Pierini (2011). The forcing, though, was aperiodic and given by:

$$G(t) = \gamma [1 + \varepsilon' f(t),] \quad (11)$$

where $\varepsilon' > 0$ is a dimensionless coefficient and $f(t)$ is a normalized, fixed realization of an Ornstein-Uhlenbeck process that has been smoothed to resemble multi-annual wind-stress forcing of the mid-latitude oceans' double-gyre circulation. Figure 17 shows $G(t)$ for $\gamma = 1$ and $\varepsilon' = 0.2$.

Figure 18 shows the evolution of two initially nearby trajectories emerging from P_2 , along with the corresponding cross-correlation, for $\gamma = 1.1$, with $\varepsilon' = 0.05$ in the two upper panels and $\varepsilon' = 0.20$ in the two lower panels; both cases have $\sigma > 1$ and the corresponding time series of P_{Ψ_3} are plotted in figures 4(h,j) of Pierini et al. (2016). The case $\varepsilon' = 0.2$ corresponds to the CPBA analyzed in detail by Pierini et al. (2016). The chaotic character of the solution is clearly visible from Fig. 18c; the cross-correlation between the two signals is plotted in Fig. 18d and it is accordingly small.

On the contrary, the case $\varepsilon' = 0.05$ corresponds to an ~~NCPBA~~NPBA: the two signals in Fig. 18a develop a large phase difference after the initial transient, but are virtually identical and remain coherent at all times. Now, unlike in Fig. 3b and




Figure 17. Aperiodic forcing $G(t)/\gamma$ of the idealized ocean model as— defined in—by Eq. (11) herein, with—and plotted using the value $\varepsilon' = 0.2$, as adopted in Pierini et al. (2016).

Figs. 9a,b, the two signals are not periodic because they are modulated by the aperiodic forcing; ~~nevertheless, but this is irrelevant; in fact,~~ the nonchaotic character of the solution can still be highlighted by the corresponding cross-correlation in Fig. 18b, whose maximum value is $e_{\max} \simeq \langle \Theta \rangle_{\Gamma} \simeq 1$, like in the autonomous and periodically forced case. Obviously, this is possible because the period of the modulated relaxation oscillation is much smaller than the time scale of the forcing; ~~this is in~~

5 ~~fact the only condition required for the applicability of this diagnostic method to aperiodically forced systems. We-~~

~~We can therefore~~ conclude that the parameter $\langle \Theta \rangle_{\Gamma}$ can be a valuable tool for monitoring the onset of chaos ~~also in certain in~~ aperiodically forced systems ~~-as well. For example, this diagnostic method can be applied to study the onset of chaos in systems that possess a drift mimicking global warming and other climate change scenarios (as done, for instance, in Drótos et al., 2015).~~

10 6 Summary and conclusions

In this paper, we studied the transition from nonchaotic to chaotic PBAs in a nonautonomous system whose autonomous limit is ~~not chaotic non chaotic, and in which, therefore, chaos is induced by the periodic forcing.~~ The illustrative example chosen for this general problem was a low-order quasigeostrophic model of the mid-latitude wind-driven ocean circulation, subject to periodic forcing. The model was described, and connected with previous work, in Sect. 2.

15 We first investigated, in Sect. 3, the autonomous system, following up on the work of Pierini (2011), who obtained its ~~bifurcation diagram- governing equations and analyzed their solutions.~~ Here, ensemble simulations based on a large number of initial data and the calculation of the system's entropy allowed us to determine novel and interesting features of the system subject to steady forcing.

To do so, we used the metric σ that was introduced by Pierini et al. (2016) and measures the time average of the distance
20 between two trajectories that are very close at $t = 0$ on a subset Γ of phase space. The analysis based on this metric yielded regions in Γ with σ -values that can be either larger or less than unity. The spatial structure of these regions, cf. Figs. 2c,d here, is very similar to that of the nonautonomous case investigated by Pierini et al. (2016), as seen in Fig. 6 therein. This similarity suggests that the nonautonomous behavior of a dynamical system is profoundly influenced by the convergence properties of




Figure 18. Role of the cross-correlation diagnostics in characterizing chaotic behavior for an aperiodically forced system, given by Eqs. (2) and (11); $\gamma = 1.1$. (a) Time series evolution of Ψ_3 for $\varepsilon' = 0.05$ in Eq. (11); and (b) corresponding cross-correlation. (c,d) Same as (a,b) but for $\varepsilon' = 0.2$. The trajectories initialized at P_2 are in red and those initialized at a nearby point are in blue.

trajectories initialized off the attractor in the autonomous case; this finding, in turn, implies that ensemble simulations are very helpful in studying said properties.

We investigated next, still in the autonomous case, the apparent paradox of regions with $\sigma > 1$ coexisting in the periodic regime of $\gamma = 1.1$ with the expected regions of $\sigma < 1$. A large number of trajectories emanating from the small square box of Fig. 4c, for which $\sigma > 1$, evolves into the extended red line shown in the same figure at a given time, $t = 300$ yr: this line belongs to the periodic attractor shown in Fig. 1b and the entropy evolution along it oscillates periodically, cf. Fig. 4d; but it is clearly distinct from the chaotic attractor apparent as the green cloud of points in the same figure panel. Further evidence for the stability of the trajectories in this periodic case with $\sigma > 1$ is provided by Fig. 5a.

We conclude that sensitive phase dependence to initial data in a periodic regime may be present if the trajectories are initialized off the attractor, but that it disappears once the trajectories have converged onto the attractor. Clearly, generic sensitive dependence on initial data is, therewith, a necessary but not sufficient condition for chaotic behavior.

In Sect. 4, we studied the PBAs-of-onset of chaos in the system subject to the periodic forcing given by Eq. (3) in the case of $\gamma = 1.1$, in which the system is non chaotic in the autonomous limit, so that chaos is induced by the periodic forcing. The

PBAs were analyzed at first for four different sinusoidal-forcing amplitudes, with $\epsilon = 0, 0.05, 0.10$, and 0.2 , while using the same $\gamma = 1.1$ and $T_p = 30$ yr.

We found that the first two cases, namely $\epsilon = 0$ and 0.05 , are ~~not non~~ chaotic, while the other two, namely $\epsilon = 0.10$ and 0.20 , are chaotic. A large number of trajectories emanating from the small square box where $\sigma > 1$ in Figs. 8a–d evolves —
5 depending on the value of ϵ — into two very different fixed-instant subsets of the model’s PBA, with the snapshot taken at $t = 400$ yr, i.e. after convergence of the trajectories to the PBA. In the first two cases, this snapshot is a curved-line segment that belongs to the PBA, while in the latter two cases it covers the whole PBA, due to the typical mixing property of chaos.

An analysis of the trajectories, as shown in Fig. 9, for instance, indicates that the transition to chaos occurs via an intermittent emergence of periodic oscillations with different phases; see again Fig. 9c. We have shown that, for values of ϵ in the chaotic
10 regime just above the transition, the periodic character of the system is still predominant, but the external forcing is now sufficiently strong to cause a trajectory’s occasionally shifting to a phase space region in which a different phase prevails: since the shifts are very sensitive to the initial data, the result is a chaotic trajectory characterized by irregular jumps of the oscillatory solutions between distinct phases.

In Sect. 4.2, we introduced a novel diagnostic method for the study of the transition between nonchaotic and chaotic behavior
15 as the amplitude ϵ of the periodic forcing increases. The method’s basic idea is that in a nonchaotic regime ~~all trajectories are~~ periodic any couple of initially nearby trajectories emerging from Γ remain coherent at all times, while in a chaotic regime aperiodic diverging trajectories emerge from ~~at least some a~~ subset of Γ ; ~~in which necessarily $\sigma > 1$~~ . Hence, a systematic recognition of the ~~periodic or aperiodic~~ character of all the trajectories allows one to diagnose which of these two types of behavior occurs or whether the two actually coexist.

A simple and robust way to do this is to compute the cross-correlation $c(X, Y, X', Y', \tau)$ at lag τ between two initially nearby
20 trajectories started at (X, Y) and (X', Y') in Γ , then compute its maximum ~~$e_{\max}(X, Y, X', Y') = \Theta(X, Y)$ value~~ $\Theta(X, Y)$ over τ . If $\Theta(X, Y) \simeq 1$ everywhere in Γ , then the system is ~~periodic~~ non chaotic, and is therefore periodic under periodic forcing; on the contrary, if Θ is appreciably smaller than unity in some subset of Γ , the system is chaotic. The diagram of the average $\langle \Theta \rangle_{\Gamma}(\epsilon)$ of $\Theta(X, Y)$ over Γ , as plotted in Fig. 13, reveals an abrupt transition to chaos at $\epsilon_c \simeq 0.09$.

This cross-correlation–based method has also been applied to the autonomous system ~~in Sect. 5.1 and to the aperiodically~~
25 ~~forced system studied by Pierini et al. (2016) since, in fact, the conditions under which the method applies are satisfied in these~~ two cases, in which the conditions required for the periodically-forced case do apply as well. ~~For the autonomous system~~ with steady forcing, the The diagram of $\langle \Theta \rangle_{\Gamma}(\gamma)$ in Fig. 14 reveals that chaotic dynamics occurs at first within an extremely restricted range centered at the global bifurcation point $\gamma = \gamma_c = 1$, which separates small-amplitude, fairly smooth oscillations
30 below γ_c from large-amplitude relaxation oscillations above it. A considerably broader range of chaotic behavior occurs in the autonomous case for values of γ greater than a threshold $\gamma_0 = 1.3475$.

~~In the aperiodic case, the cross-correlation method seems to apply at least~~ We have then applied the cross-correlation–based
method to the aperiodically forced system studied by Pierini et al. (2016). Our results show that, in fact, this method can be
applied to systems subject to aperiodic forcing when the system’s intrinsic periodicity and the characteristic time scale of the
35 external forcing are sufficiently well separated from each other, which is the case ~~investigated by in~~ Pierini et al. (2016), cf.

Fig. 17 here. Once more, the cross-correlations in Figs. 18c,d agree remarkably well with the character of the model trajectories in Figs. 18a,b.

Finally, the coexistence of local PBAs with chaotic vs. nonchaotic behavior within a global PBA — as first described by Pierini et al. (2016) in the aperiodic-forcing case — was confirmed here for the periodically forced case, cf. Figs. 6 and 11.

5 This situation was explored in greater depth in App. A for an even simpler, weakly dissipative nonlinear model, namely a Van der Pol–Duffing oscillator (e.g., Jackson, 1991), and additional references were given for this type of PBA bistability.

Overall, this paper provides additional insights into the complex and varied behavior that arises even in highly idealized atmospheric, oceanic and climate models from the interaction of nonlinear intrinsic dynamics with various types of external forcing. In addition, it stresses the importance of using the framework of nonautonomous dynamical systems and of their PBAs

10 for a deeper understanding of this complexity and variety.

Acknowledgements. SP would like to thank the "Università di Napoli Parthenope" for having supported his visit to the University of California at Los Angeles in August 2017 through grants D.R. 539 (29-6-2016) ~~and~~, D.R. 953 (28-11-2016, DSTE315) ~~and for the partial support provided by the grant DSTE315B. SP and MG gratefully acknowledge partial support from the MOMA project (PNRA16-00196-B) of the Italian P.N.R.A.~~ This work has been partially supported by the Office of Naval Research (ONR) Multidisciplinary University Research Initiative (MURI) grants N00014-12-1-0911 and N00014-16-1-2073 (MDC and MG). MDC also ~~also~~ gratefully acknowledges support from the National Science Foundation (NSF) grants OCE-1243175, OCE-1658357 and DMS-1616981.

15

Appendix A: Coexistence of pullback attractors in a Van der Pol-Duffing oscillator

The purpose of this appendix is to provide further insight into the coexistence of local PBAs with quite different stability properties, as illustrated in the main text by Figs. 6 and 11. In complex autonomous systems, several local attractors may coexist for a given set of the system's parameters; each of these attractors possesses attracting sets of initial data that are typically separated by fractal boundaries (Grebogi et al., 1987). Basins of attraction with fractal boundaries have consequences for predictability: uncertainties on the initial state x_0 may result in different types of dynamical behavior, depending on which basin x_0 lies in; see, for instance, Roques and Chekroun (2011). When the number of the coexisting attractors is two, one speaks of bistability, and multistability refers colloquially to more than two coexisting attractors.

20

Our goal here is to illustrate how multistability for nonautonomous systems manifests itself unambiguously through the existence of disjoint local PBAs. In the case of periodically forced systems, such as considered in this article, similar results can be inferred, of course, from the analysis of Poincaré maps. Nevertheless, the presence of other frequencies in the internal dynamics, the external forcing or the noise may render the analysis of Poincaré maps difficult, whereas the framework of PBAs includes naturally such additional levels of complexity (Chekroun et al., 2018). Pierini et al. (2016), for instance, demonstrated already the usefulness of this framework in the context of bistability.

25

30

Furthermore, the purpose of this Appendix is also to illustrate that multistability of local PBAs arises not only for our quasi-geostrophic model, as discussed in the paper's main text. More generally, PBA coexistence occurs fairly often for externally

forced systems, albeit a careful analysis of the flow’s dependence on initial data may be required in practice in order to conclude on multistability.

A paradigm of multistability is provided by dissipative nonlinear systems that become Hamiltonian in the limit of vanishing dissipation, as is the case, for instance, in celestial mechanics (e.g., Ghil and Wolansky, 1992). In this situation, it is expected that the number of coexisting attractors exceeds any fixed bound in approaching this limit, as documented for various nearly-integrable maps and flows, cf. (Feudel et al., 1996; Zaslavsky and Edelman, 2008; Celletti, 2009; Pisarchik and Feudel, 2014; Dudkowski et al., 2016) and references therein.

To illustrate this multistability phenomenon, we consider the following periodically forced Van der Pol–Duffing oscillator, given by the second-order nonlinear ODE

$$\ddot{x} = \mu(1 - \dot{x}^2)x - bx^3 + F \sin(\omega t), \quad (\text{A1})$$

where μ , b , F and ω are positive constants that determine the dynamical behavior of the the system. This system is non-autonomous and its PBAs are analyzed hereafter in the (x, \dot{x}) -plane. This nonlinear ODE arises in various applications such as in engineering, electronics, biology, and neurology (Jackson, 1991; Kozlov et al., 1999; Kuznetsov et al., 2009). It combines the nonlinearity of the dissipation $-\mu\dot{x}^2x$, which characterizes the Van der Pol (1920) oscillator with that of the internal force $-bx^3$, which characterizes the Duffing (1918) oscillator.

Multistability was already numerically documented for Eq. (A1) by relying on Poincaré maps (Venkatesan and Lakshmanan, 1997; Dudkowski et al., 2016). In our calculations, we have followed (Dudkowski et al., 2016) and assumed $\mu = 0.2$, $F = b = 1.0$, and $\omega = 0.955$. While this parameter regime does not correspond to the limit of vanishing dissipation that was mentioned above, it still allows for a coexistence of PBAs, given a careful choice of initial states.

The numerical protocol followed to analyze multistability for Eq. (A1) in terms of PBAs is described next. First, the initial data have been drawn uniformly in the two disjoint domains D_1 and D_2 of the (x, \dot{x}) -plane, with

$$D_1 = [-2.5, -1.5] \times [-2.5, -1.5], D_2 = [-0.34, -0.33] \times [-0.34, -0.33]. \quad (\text{A2})$$

6 000 initial data from each domain were propagated according to Eq. (A1). The ODE was integrated using a Runge-Kutta fourth-order method with a constant time step $\Delta t = 10^{-2}$, generating a total of 12 000 trajectories, and keeping 10^6 data points for each, after removal of the transient.

The majority of the initial data taken in the smaller domain D_2 leads to a quasiperiodic orbit, while each of the 6 000 initial data taken in D_1 leads to a chaotic trajectory — as do a few “rare” initial data from D_2 . An example of such a quasiperiodic trajectory is shown in blue in Fig. A1(a), within the (x, \dot{x}) phase plane. This blue trajectory is superimposed upon a red, chaotic trajectory emanating from an initial point taken in D_1 . The corresponding power spectra are shown in Fig. A1(b), with the same blue and red color coding. The chaotic trajectory is clearly more diffuse within the phase plane than its quasiperiodic counterpart, and its power spectrum is quite a bit noisier. Both of these features are well known to be symptomatic of deterministic chaos (Eckmann and Ruelle, 1985).

By allowing the quasiperiodic trajectories that emanate from D_2 to evolve up to $t = 2\,000$, one obtains the set of blue points shown in Fig. A2. Somewhat surprisingly, this set does not form a closed curve: ~~it is actually the union of quasiperiodic~~

orbits that—while sharing the same fundamental combinations of frequencies shown in each blue dot in Fig. A2 corresponds actually to the state at $t = 2\,000$ in the phase plane of a quasiperiodic orbit. One such orbit is represented in blue in Fig. A1(b) (for the blue curve)—may exhibit a power spectrum that contains a multitude of local variations reminiscent of those exhibited by power spectra of the chaotic orbits, i. e. similar to those a), after removal of the transient dynamics. Each blue dot in Fig. A2 corresponds to a different quasiperiodic orbit, whose frequency characteristics may slightly change from one blue dot to another. All these quasiperiodic orbits share, however, a spectral signature that resembles the one shown by the red-blue curve in Fig. A1(b). Such quasiperiodic orbits are wrapped onto a torus with a larger minor radius that results typically in broader strips in the phase plane (not shown) than those displayed by the blue orbit.

To illustrate further the distinction between quasiperiodic and chaotic orbits, the return maps for the the minima of the $x(t)$ -variable have been computed. As is well-known (e.g., Strogatz, 2018), if the return map contains just one point, the solution is periodic in time, with all minima having the exact same value, and the period of the oscillation can be estimated by calculating the time interval between two consecutive minima. If the return map contains continuous-looking curves that fill up with more and more points as the length of the orbit increases, the solution is quasiperiodic, while the presence of folds and self-similarity in the return map provides strong evidence for chaotic solutions. For the blue and red trajectories of Fig. A1(a), we plot the corresponding return maps in Figs. A3(a) and (b), respectively. The two plots clearly discriminate between the quasiperiodic nature of the former and the chaotic one of the latter solution.

The initial data taken in D_1 , when allowed to flow according to Eq. (A1), lead to a totally different local PBA that is formed by the red points shown in Fig. A2. Although the approximation of this local PBA shown here is relatively sparse, one can clearly discern the fact that its constitutive points are arranged according to a stretching and folding pattern that is typical of nonlinear, chaotic dynamics in the autonomous, as well as in the nonautonomous setting (Chekroun et al., 2018).

The features that we find here to be exhibited by the local chaotic PBA are highly reminiscent of those that were obtained, in this deterministic case, by applying a standard Poincaré section analysis, cf. (Dudkowski et al., 2016, Fig. 17(e))Dudkowski et al. (2016, Fig. 17). In the presence of noise, though, the fine structure of the PBAs that results from stretching and folding in phase space, is still captured by the PBA framework (Chekroun et al., 2018), whereas a Poincaré-map approach would lead only to a cloud of points with no particular geometric structure. This statement was numerically illustrated in (Chekroun et al., 2011) by contrasting, by Chekroun et al. (2011) in their Fig. 7, by contrasting the upper-right panel vs. the six lower panels of the figure.

Finally, we emphasize that it is not the disjointness of the two domains, D_1 and D_2 , that leads to the two distinct types of PBA, chaotic and quasiperiodic.² Indeed, as mentioned earlier, even though the area of D_2 is small, it still contains initial data whose evolution lands within the local PBA associated with chaos, i.e., with the other red points shown in Fig. A2.

30 *Competing interests.* Stefano Pierini is a member of the editorial board of the journal. The authors declare no conflict of interest.

²Other such quasiperiodic PBAs exist (not shown), whereas only one chaotic PBA seems to exist for the parameter regime analyzed herein.




Figure A1. Coexistence of local forward attractors. (a) Quasiperiodic forward attractor (blue) and chaotic attractor (red). (b) Power spectrum associated with the quasiperiodic orbit (blue) and the chaotic one (red).

References

- Arnold, L.: Random Dynamical Systems, Springer, 1998.
- Bódai, T. and Tél, T.: Annual variability in a conceptual climate model: Snapshot attractors, hysteresis in extreme events, and climate sensitivity, *Chaos*, 22, 023 110, 2012.
- 5 Bódai, T., Károlyi, G., and Tél, T.: Driving a conceptual model climate by different processes: Snapshot attractors and extreme events, *Phys. Rev. E*, 87, 022 822, 2013.
- Carrassi, A., Ghil, M., Trevisan, A., and Uboldi, F.: Data assimilation as a nonlinear dynamical systems problem: Stability and convergence of the prediction-assimilation system, *Chaos*, 18, <https://doi.org/10.1063/1.2909862>, 2008a.
- Carrassi, A., Trevisan, A., Descamps, L., Talagrand, O., and Uboldi, F.: Controlling instabilities along a 3DVar analysis cycle by assimilating
 10 in the unstable subspace: a comparison with the EnKF, *Nonlin. Processes Geophys.*, 15, 503–521, 2008b.
- Carvalho, A., Langa, J. A., and Robinson, J.: *Attractors for Infinite-Dimensional Non-Autonomous Dynamical Systems*, Springer, 2012.
- Celletti, A.: Periodic and quasi-periodic attractors of weakly-dissipative nearly-integrable systems, *Regular Chaotic Dyn.*, 14, 49–63, 2009.




Figure A2. Coexistence of local PBAs. The initial data leading to quasiperiodic (resp. chaotic) orbits are taken from the small domain D_2 (resp. D_1) described by Eq. (A2). The snapshot of the PBAs shown here is taken at the fixed time $t = 2\,000$.

- Chekroun, M. D., Simonnet, E., and Ghil, M.: Stochastic climate dynamics: Random attractors and time-dependent invariant measures, *Physica D*, 240, 1685–1700, 2011.
- Chekroun, M. D., Ghil, M., and Neelin, J. D.: Pullback attractor crisis in a delay differential ENSO model, in: *Advances in Nonlinear Geosciences*, edited by A. Tsonis, pp. 1–33, Springer, https://link.springer.com/chapter/10.1007/978-3-319-58895-7_1, 2018.
- 5 De Cruz, L., Schubert, S., Demaeyer, J., Lucarini, V., and Vannitsem, S.: Exploring the Lyapunov instability properties of high-dimensional atmospheric and climate models, *Nonlin. Processes Geophys.*, 25, 387–412, 2018.
- Drótos, G., Bóday, T., and Tél, T.: Probabilistic concepts in a changing climate: A snapshot attractor picture, *J. Clim.*, 28, 3275–3288, 2015.
- Drótos, G., Bóday, T., and Tél, T.: On the importance of the convergence to climate attractors, *Eur. Phys. J. Special Topics*, 226, 2031–2038, 2017.
- 10 Dudkowskii, D., Jafari, S., Kapitaniak, T., Kuznetsov, N. V., Leonov, G. A., and Prasad, A.: Hidden attractors in dynamical systems, *Physics Reports*, 637, 1–50, 2016.
- Duffing, G.: *Erzwungene Schwingungen bei veränderlicher Eigenfrequenz und ihre technische Bedeutung*, vol. 41/42 of *Sammlung Vieweg*, R. Vieweg & Sohn, Braunschweig, 1918.
- Eckmann, J.-P. and Ruelle, D.: Ergodic theory of chaos and strange attractors, *Rev. Modern Phys.*, 57, 617–656, 1985.




Figure A3. Return maps of the minima of $x(t)$ for (a) the quasiperiodic orbit shown in blue in Fig. A1(a), and for (b) the chaotic orbit shown in red in Fig. A1(a); see text for details.

Feudel, U., Grebogi, C., Hunt, B. R., and Yorke, J. A.: Map with more than 100 coexisting low-period periodic attractors, *Physical Review E*, 54, 71, 1996.

Ghil, M.: Cryothermodynamics: the chaotic dynamics of paleoclimate, *Physica D*, 77, 130–159, 1994.

Ghil, M.: A mathematical theory of climate sensitivity or, How to deal with both anthropogenic forcing and natural variability?, in: *Climate Change: Multidecadal and Beyond*, edited by Chang, C. P., Ghil, M., M., L., and Wallace, J. M., pp. 31–51, World Scientific Publ. Co./Imperial College Press, 2015.

Ghil, M.: The wind-driven ocean circulation: Applying dynamical systems theory to a climate problem, *Discr. Cont. Dyn. Syst. A*, 37, 189–228, 2017.

Ghil, M. and Wolansky, G.: Non-Hamiltonian perturbations of integrable systems and resonance trapping, *SIAM Journal on Applied Mathematics*, 52, 1148–1171, 1992.

Ghil, M., Chekroun, M. D., and Simonnet, E.: Climate dynamics and fluid mechanics: Natural variability and related uncertainties, *Physica D*, 237, 2111–2126, 2008.

Grebogi, C., Ott, E., and Yorke, J. A.: Chaos, strange attractors, and fractal basin boundaries in nonlinear dynamics, *Science*, 238, 632–638, 1987.

Hilborn, R. C.: *Chaos and Nonlinear Dynamics*, Oxford University Press, 2000.

Jackson, E. A.: *Perspectives of Nonlinear Dynamics*, Cambridge University Press, New York, 1991.

- Jiang, S., Jin, F.-F., and Ghil, M.: Multiple equilibria, periodic, and aperiodic solutions in a wind-driven, double-gyre, shallow-water model, *J. Phys. Oceanogr.*, 25, 764–786, 1995.
- Kloeden, P. E. and Rasmussen, M.: *Nonautonomous Dynamical Systems*, 176, Amer. Math. Soc., 2011.
- Kozlov, A., Sushchik, M., Molkov, Y., and Kuznetsov, A.: Bistable phase synchronization and chaos in system of coupled Van der Pol-Duffing oscillators, *Int. J. Bifurcation Chaos*, 9, 2271–2277, 1999.
- Kuznetsov, A., Stankevich, N., and Turukina, L.: Coupled van der Pol–Duffing oscillators: Phase dynamics and structure of synchronization tongues, *Physica D*, 238, 1203–1215, 2009.
- Le Treut, H. and Ghil, M.: Orbital forcing, climatic interactions, and glaciation cycles, *J. Geophys. Res.*, 88, 5167–5190, <https://doi.org/10.1029/JC088iC09p05167>, <http://dx.doi.org/10.1029/JC088iC09p05167>, 1983.
- Lucarini, V., Ragone, F., and Lunkeit, F.: Predicting climate change using response theory: Global averages and spatial patterns, *J. Stat. Phys.*, 166, 1036–1064, 2017.
- Manneville, P. and Pomeau, Y.: Intermittency and the Lorenz model, *Phys. Lett. A*, 75, 1–2, 1979.
- Nicolis, G.: *Introduction to Nonlinear Science*, Cambridge University Press, 1995.
- Ott, E.: *Chaos in Dynamical Systems*, Cambridge University Press, 2002.
- Pierini, S.: A Kuroshio Extension system model study: Decadal chaotic self-sustained oscillations, *J. Phys. Oceanogr.*, 36, 1605–1625, 2006.
- Pierini, S.: Low-frequency variability, coherence resonance, and phase selection in a low-order model of the wind-driven ocean circulation, *J. Phys. Oceanogr.*, 41, 1585–1604, 2011.
- Pierini, S.: Stochastic tipping points in climate dynamics, *Phys. Rev. E*, 85, 027 101, 2012.
- Pierini, S.: Ensemble simulations and pullback attractors of a periodically forced double-gyre system, *J. Phys. Oceanogr.*, 44, 3245–3254, 2014.
- Pierini, S. and Dijkstra, H. A.: Low-frequency variability of the Kuroshio Extension, *Nonlin. Processes Geophys.*, 16, 665–675, 2009.
- Pierini, S., Dijkstra, H. A., and Riccio, A.: A nonlinear theory of the Kuroshio Extension bimodality, *J. Phys. Oceanogr.*, 39, 2212–2229, 2009.
- Pierini, S., Ghil, M., and Chekroun, M. D.: Exploring the pullback attractors of a low-order quasigeostrophic ocean model: the deterministic case, *J. Climate*, 29, 4185–4202, 2016.
- Pisarchik, A. N. and Feudel, U.: Control of multistability, *Physics Reports*, 540, 167–218, 2014.
- Pomeau, Y. and Manneville, P.: Intermittent transition to turbulence in dissipative dynamical systems, *Commun. Math. Phys.*, 74, 189–197, 1980.
- Rasmussen, M.: *Attractivity and Bifurcation for Nonautonomous Dynamical Systems*, Springer, 2007.
- Romeiras, F. J., Grebogi, C., and Ott, E.: Multifractal properties of snapshot attractors of random maps, *Phys. Rev. A*, 41, 784, 1990.
- Roques, L. and Chekroun, M. D.: Probing chaos and biodiversity in a simple competition model, *Ecological Complexity*, 8, 98–104, 2011.
- Shannon, C. E.: The mathematical theory of communication, *Bell Syst. Tech. J.*, 27, 379–423, 623–656, 1948.
- Strogatz, S. H.: *Nonlinear Dynamics and Chaos*, Westview Press, 1994.
- Strogatz, S. H.: *Nonlinear Dynamics and Chaos: with Applications to Physics, Biology, Chemistry, and Engineering*, CRC Press, 2018.
- Sushama, L., Ghil, M., and Ide, K.: Spatio-temporal variability in a mid-latitude ocean basin subject to periodic wind forcing, *Atmosphere-Ocean*, 45, 227–250, doi:10.3137/ao.450404, 2007.
- Tél, T. and Gruiz, M.: *Chaotic Dynamics*, Cambridge University Press, 2006.

- Trevisan, A. and Palatella, L.: On the Kalman Filter error covariance collapse into the unstable subspace, *Nonlin. Processes Geophys.*, 18, 243–250, <https://doi.org/10.5194/npg-18-243-2011>, 2011.
- Trevisan, A. and Uboldi, F.: Assimilation of standard and targeted observations within the unstable subspace of the observation-analysis-forecast cycle system, *J. Atmos. Sci.*, 61, 103–113, [https://doi.org/10.1175/1520-0469\(2004\)061<0103:AOSATO>2.0.CO;2](https://doi.org/10.1175/1520-0469(2004)061<0103:AOSATO>2.0.CO;2), 2004.
- 5 Van der Pol, B.: A theory of the amplitude of free and forced triode vibrations, *Radio Rev.*, 1, 701–710, 1920.
- Van der Pol, B.: On relaxation-oscillations, *The London, Edinburgh and Dublin Phil. Mag. and J. Sci.*, 2, 978–992, 1926.
- Vannitsem, S.: Stochastic modelling and predictability: analysis of a low-order coupled ocean–atmosphere model, *Phil. Trans. Roy. Soc. A*, 372, 20130282, 2014.
- Vannitsem, S. and De Cruz, L.: A 24-variable low-order coupled ocean–atmosphere model: OA-QG-WS v2, *Geos. Model Dev.*, 7, 649–662,
10 2014.
- Venkatesan, A. and Lakshmanan, M.: Bifurcation and chaos in the double-well Duffing–Van der Pol oscillator: Numerical and analytical studies, *Phys. Rev. E*, 56, 6321, 1997.
- Zaslavsky, G. M. and Edelman, M.: Superdiffusion in the dissipative standard map, *Chaos*, 18, 033116, 2008.